

Bad River Tribe - Fiber Optic Labor Request Pricing - Must add up to Total Sum Pricing

See "Exhibit 1" for specific details on materials and items to be included in pricing.

Item	Description	Quantity	U of M	Unit Price	Total Price	Lead Time
1	Supply and install 2" underground plow duct 2" inside diameter first-run SDR-11 HDPE Orange smooth exterior/smooth interior with mule tape for pulling and future use.	53,012	L.F		\$ -	
2	Supply and install ¾" underground plow duct ¾" inside diameter first-run SDR-13.5 HDPE Orange smooth exterior/smooth interior with mule tape and for future use. (This is for Drops)	39,577	L.F		\$ -	
3	Supply and install ¾" Schedule 40 PVC to attach to homes.	3,390	L.F		\$ -	
4	Supply and Install Tracer Wire on Outside of Duct	92,589	L.F		\$ -	
5	Supply and Install 30"x48"x36" Handhole with Two-piece lid.	27	EACH		\$ -	
6	Supply and install 17"x30"x18" Pencil or equivalent plastic handholes	128	EACH		\$ -	
7	Supply and Install 9" Round Handhole – Tier22 (Flowerpot's)	54	EACH		\$ -	
8	Supply and Install Copper Clad Ground Rod	155	EACH		\$ -	
9	Supply and Install Split Duct Plugs	360	EACH		\$ -	
10	Supply and install ¾" Simplex Duct Plug	339	EACH		\$ -	
11	Supply and Install Fiber Optic Cable Labels	198	EACH		\$ -	
12	Pour 4'x4'x6" Pad with (2) 2" Ducts Stubbed out	4	EACH		\$ -	
13	Install 4 Splitter Cabinets onto concrete pad	4	EACH		\$ -	
14	Pull Cable and Mule Tape through new 2" Duct.	53,012	L.F		\$ -	
15	Pull Drop Cable through new ¾" Duct and attach drop to NID	39,577	L.F		\$ -	
16	Install NIDS on Home	339	EACH		\$ -	
17	Supply and Install Commscope 450D Splice Cases w/4 Total Trays	4	EACH		\$ -	
18	Outdoor Fusion Splices	602	EACH		\$ -	
19	Rock Adder Per L.F.	1	L.F		\$ -	
20	Cobble Adder Per L.F	1	L.F		\$ -	
21	Concrete Restoration per Sq. Ft.	1	SQ.FT		\$ -	
				Grand Total	\$ -	